

## CSP Plant Construction, Start-up, and O&M Best Practices Study

### Session 4 - Past Experience with CSP

#### Project Team

Mark S. Mehos – NREL (Principal Investigator)

Hank Price – Solar Dynamics (Project Lead)

Robert Cable - Consultant

David Kearney – KA Solar

Bruce Kelly – Solar Dynamics

Greg Kolb - Consultant

Fred Morse – Morse Associates, Inc.

#### Cost Share Partners



# Project Intent, Objective and Audience

---

- **Intent** - to help developers, EPCs and O&M providers avoid the detrimental practices that have hindered some projects in the recent early commercial growth stage of power plants using CSP technology.
- **Objective** - to publish best practices and lessons learned from the engineering, procurement, construction, commissioning, operation and maintenance of existing parabolic trough and central receiver plants.
- **Audience** - developers, investors, lenders, off-takers, EPC firms, vendors, O&M providers, and policy makers.
- **R&D** - Identify issues that could benefit from further R&D

# CSP Stakeholder Participation

---

Aalborg

Abengoa

ACWA

Advisian/Worley Parsons

Atlantica Yield

BrightSource

Cerro Dominador

ChemTreat

CMI

Cobra

CSP Services

DEWA

DLR

Gemasolar plant

Fichtner

Flowserve

FTI

Huiyin Group

La Africana plant

Lointek

MASEN

Mott MacDonald

Nevada Solar One

NRG

OCA Global

Parsons Group

Sargent & Lundy

SBP

SENER

SolarReserve

SolEngCo

SUNCAN

Terra-Gen (SEGS VIII/IX)

TSK

Virtual Mechanics

Vast Solar

## CSP Facilities

90 commercial tower & trough plants in operation (+4 that have been decommissioned)

- 14 tower – 6 molten-salt, 8 steam
- 80 trough – 31 with TES

# CSP Best Practices Report

---

- **Report Structure**
  - Parabolic trough technology
  - Molten-salt tower technology
  - Operation and maintenance
  - Project organization & project execution
  
- **Report Status**
  - Sensitive information reviewed by participants
  - External expert review completed
  - Stakeholder review
  - Issue Final Report - March 2020

# General Findings

---

- **CSP plants are relatively complex power projects**
  - More of the issues identified are related to implementation in contrast to technology
  - It is best to work with experienced teams with proven solar plant track records
  - Projects need to have detailed Owner Technical Specifications (OTS)
  - Projects with more involved owners often fare better
  - Well-executed QA/QC in all phases of the development, design, procurement, construction, commissioning, and operation of a CSP power plant cannot be overstated
- **Some of the more significant problems are with conventional equipment**
  - Such as heat exchangers, valves, pumps, instrumentation, heat tracing
  - Plants need to be designed for good reliability and performance in off-design cases
- **Efforts to cut costs can end up costing projects more in the long run**
  - E.g. Low cost valves are not cheaper in the long run
- **Performance modeling has not been adequate for many projects**
  - The PM needs to handle transient plant behavior during startup and intermittent clouds to be accurate

# Molten-salt tower technology experience

---

- **Successes**
  - Long shafted salt pumps have worked well
  - Receiver technology has generally worked well
- **Areas where issues remain**
  - Salt tank and foundation design
  - Steam generator reliability over full 1% to 100% design operation
  - Heliostat and DSC System: automation, control logic and alarm management can be improved
- **Details matter**
  - Design and QC of heat tracing and insulation on salt piping
  - QC on welding
  - Good heliostat optical quality
  - Cleaning of heliostats is challenging in some regions

# Trough plant technology experience

---

- **Successes**
  - Most trough plants are operating well
  - Solar technology generally mature
- **Areas where issues remain**
  - Collector interconnection issues with ball joints, rotary joints, and flex hoses
  - Ullage system: important to remove and control degradation products
  - Designing plants for transient operation
  - Heat exchangers for SGS and TES: robust designs/good control system
  - DSC System: automation, control logic and alarm management can be improved
  - Standards need development: structural design for wind loads and collector optics
- **Performance modeling**
  - The latest advanced models offer better accuracy

# Operation & Maintenance

---

- Having an O&M team with strong prior CSP experience is highly desirable
- The O&M organizations must be prepared to take over at COD
  - Important that projects invest appropriately in the O&M mobilization, preparation, and training.
  - EPCs typically provide some training for the O&M team, but depth and timeliness is critical. Projects need to realize that the training provided by the EPC is only a portion of the overall training program required to fully mobilize the O&M organization.
  - EPCs typically prepare “O&M manuals” but the O&M team needs more advanced material at COD to operate the plant
- Having the O&M leads involved in the design, construction and commissioning of the plant is highly recommended
- O&M costs are often not budgeted correctly in financial projections



# Conclusion

---

- We believe the few remaining technology issues for parabolic trough and molten-salt tower projects are really design issues that can be resolved by appropriate engineering and equipment selection.
- Plants and equipment must be designed for the transient behavior that they will see.
- CSP projects are complex, they need to be properly managed. Best to work with experienced team with good track record.
- Desirable to have an experienced O&M team and to get them involved early.
- Accurate solar and wind resource assessment of the site is essential.
- Based on our finding, we are confident that future tower and trough plants can be built on time and budget and to perform as expected.

*Thank you for your attention!*

Hank Price, P.E.

[Hank.Price@SolarDynLLC.com](mailto:Hank.Price@SolarDynLLC.com)

+1 720-955-6404